


# LANDSCAPE PLAN

SCALE: 1:100



## PLANT/WORKS SCHEDULE

GARDEN BEDS AND LAWN AREAS INCLUDING VERGES SHALL BE RETICULATED FROM THE WATER CORPORATION INCOMING WATER SUPPLY. LANDSCAPE CONTRACTOR SHALL CONNECT RETIC TO STOP COCK LOCATED WITHIN 1000mm OF WATER METER (STOPCOCK BY BUILDER.)

RETICULATION SHALL BE FULLY AUTOMATED WITH A MAXIMUM OF 10 SPRINKLERS PER STATION.

RETICULATION TO BE DIRECTED AWAY FROM ALL WALLS AND PATHWAYS.

ALL GARDEN BEDS SHALL HAVE A MINIMUM OF 150MM DEEP QUALITY GARDEN BLEND SOIL.






SOIL SHALL BE RICH WITH BLENDED MANURES, PEAT AND TOP SOIL.

IT IS THE CONTRACTORS RESPONSIBILITY TO CHECK ALL LEVELS TO ASCERTAIN EARTHWORKS CONTENT AND ADJUST THE EXTENT OF WORK ACCORDINGLY.

ALL WORKS MUST BE CARRIED OUT IN STRICT ACCORDANCE WITH THE OCCUPATIONAL SAFETY AND HEALTH ACT 1984 AND REGULATIONS 1996.

## LEGEND

NOTE: ALL LANDSCAPING WATERED BY FULLY AUTOMATIC RETICULATION SYSTEM.



-  GREVILLEA LANIGERA MT TAMBORITHA  
150mm POT - 23 OFF
-  AGONIS FLEXUOSA NANA  
150mm POT - 35 OFF
-  GREVILLEA HONEY GEM  
200mm POT - 13 OFF
-  PYRUS USSURIENSIS  
75L BAG - 4 OFF
-  LAWN  
VELVET BUFFALO

NO	DESCRIPTION	DATE
E	CONSTRUCTION ISSUE	02.02.08
D	ADDITIONAL SHADE TREES	13.02.08
C	CONTRACT ISSUE	30.04.08
B	AMENDED SHADE TREES	31.05.08
A	BUILDING LICENSE	13.02.08

**PROPOSED OFFICES & WAREHOUSES**  
for SIKA PROPERTIES PTY LTD  
at LOT 1013 MALLAIG WAY  
CANNING VALE

DRAWING  
**LANDSCAPING PLAN**

**COMMERCIAL designMANAGEMENT**

**2 Permenter st Mt Fremantle 6159**  
 (08) 9335 2841  
 (08) 9335 2977  
 contact@designmanagement.com.au

**2** **Permenter st Mt Fremantle 6159**  
 BUILDER TO VERIFY DIMENSIONS AND SET OUT AND REFER DISCREPANCIES TO DESIGNER FOR DIRECTION  
 DRAWN BC CHECKED JDB NO. 0500  
 SCALE 1:100 DATE FEB 2008 DWG No. L31 OF L31